

**ARBORICULTURAL SURVEY
FOR A PROPOSED MIXED-USE DEVELOPMENT AT
LAND OFF FIR COVERT ROAD, TAVERHAM, NORFOLK, NR8 6HT**

Prepared For

M Scott Properties Ltd
Suite 5
Oyster House
Severalls Lane
Colchester
Essex
CO4 9PD

Report Reference Number: 3551,EC,AR,DS/P1 ARB/TC,RF,KL/04-12-18/V1
Project Number: 3551,EC,AR,DS
Issue Number: 1
Issue Date: 04 December 2018



ADDRESS

Brightwell Barns, Ipswich Road, Brightwell, Suffolk, IP10 0BJ

TELEPHONE

01603 298 076

FAX

01603 298 075

WEBSITE

www.geosphere-environmental.co.uk

DOCUMENT ISSUED RECORD

Report Number:	3551,EC,AR,DS/P1 ARB/,TC,RF,KL/04-12-18/V1
Client:	M Scott Properties Ltd
Project:	Land Off Fir Covert Road, Taverham, Norfolk, NR8 6HT
Project Number:	3551,EC,AR,DS
Report Type:	Arboricultural Survey
Date of Report:	04 December 2018

Prepared by: Tom Cox
Ecologist
Date: 04 December 2018

Reviewed by: Richard Fenna
Arboricultural and
Ecological
Consultant
Date: 04 December 2018

Authorised by: Katie Linehan
Technical Director
Date: 04 December 2018

Prepared by: Geosphere Environmental Ltd, Brightwell Barns, Ipswich Road, Brightwell, Suffolk, IP10 0BJ.
Telephone (01603) 298076. www.geosphere-environmental.co.uk

Confidentiality, Copyright and Reproduction: This document has been prepared by Geosphere Environmental Ltd in connection with a contract to supply goods and/or services and is submitted only on the basis of strict confidentiality. The contents must not be disclosed to third parties other than in accordance with the terms of the contract. Geosphere Environmental Ltd accepts no responsibility whatsoever to third parties to whom this report, or any part thereof, is made known. Any such party relies upon the report at their own risk.

REVISION RECORD

Revision	Date	Document	Prepared By:	Admin

AMENDMENT RECORD

Revision	Date	Amendments

EXECUTIVE SUMMARY

Report Description	<p>Geosphere Environmental Limited was commissioned by M Scott Properties Ltd, to undertake an arboricultural survey of Land Off Fir Covert Road, Taverham, Norfolk, NR8 6HT.</p> <p>The site is located at National Grid Reference (NGR) TG 1600 1546. The report relates to the assumed redevelopment of the site for residential use.</p> <p>The site covers an area of approximately 14 hectares (ha). This and the immediate surrounding area were surveyed.</p>
Summary of Main Findings	<p>The Tree Constraints Plan Drawing ref. 3551,EC,AR,DS/001/Rev 0 in Appendix 6, shows the locations of all the trees surveyed with the canopy and root protection area plotted on the plan.</p> <p>A total of thirty-three trees and twelve groups of trees were surveyed.</p> <p>Seven trees and two groups of trees were classed as category A trees. Sixteen trees and six groups of trees were classified as category B trees. Ten trees and four groups of trees were classified as category C trees. No trees were categorised as category U trees.</p> <p>The BGS digital mapping indicated that the site comprised of a bedrock layer of Chalk with a recorded superficial layer of Sheringham Cliffs Formation (sand and gravel).</p> <p>It is advisable to contact the local authority regarding Tree Preservation Orders and Conservation Areas before any tree works are carried out, to determine if any protection is in place on site.</p>
Preliminary Impact Assessment	<p>The residential properties are to be situated within the existing fields. The proposed development plans should not include any access roads, driveways, or services within the root protection areas of trees.</p> <p>Sections of hedgerow will have to be removed to construct the access road. The road should be designed to avoid the root protection areas of as many trees as possible, however category A trees should be protected as a priority.</p>
Recommendations	<p>The Tree Constraints Plan should be consulted to ensure that the constraints posed by the trees are taken into account when designing the proposed development. For example, retained trees could be incorporated within the proposed residential gardens or within proposed public open space.</p> <p>A Tree Retention Plan and a Tree Protection Plan will need to be designed once the layout of the development area has been finalised. This will include locations of trees to be retained, finalised locations of protective barriers, construction exclusion zones and any other protection that trees will require prior to commencement of construction. An Arboricultural Method Statement, Arboricultural Impact Assessment and Tree Management Plan should be supplied with the Tree Protection Plan.</p>

CONTENTS

Page No.

DOCUMENT ISSUED RECORD	1
EXECUTIVE SUMMARY	2
1. INTRODUCTION	4
1.1 General	4
1.2 Aims	4
2. TECHNICAL APPROACH	5
2.1 Arboricultural Survey	5
2.2 Soil Assessment	5
2.3 Site Specific Limitations	5
3. TREE SURVEY	6
3.1 Site Description	6
3.2 Tree Survey Results	6
3.3 Tree Constraints Plan	6
3.4 Soil Assessment	7
3.5 Permissions and Council Restrictions	7
4. PRELIMINARY ARBORICULTURAL IMPACT ASSESSMENT	8
4.1 Proposed Development	8
4.2 Potential impacts and avoidance	8
4.3 Tree Management	8
4.3.1 Tree Pruning	9
4.3.2 Tree Planting	9
5. RECOMMENDATIONS	10

APPENDICES

APPENDIX 1 – REPORT LIMITATIONS AND CONDITIONS

APPENDIX 2 – REFERENCES

APPENDIX 3 – TREE SURVEY SCHEDULE

APPENDIX 4 – SURVEY SCHEDULE DESCRIPTIONS

APPENDIX 5 – KEY TO SCIENTIFIC NAMES

APPENDIX 6 – DRAWINGS

1. INTRODUCTION

1.1 General

Geosphere Environmental Limited was commissioned by M Scott Properties Ltd, to undertake an Arboricultural Survey of the site at Land Off Fir Covert Road, Taverham, Norfolk, NR8 6HT. Any limitations and conditions pertaining to the report are stated within Appendix 1, with a full list of technical references provided within Appendix 2.

An arboricultural survey was undertaken in the wider area, this report relates specifically to an area of land, adjacent to Taverham Football Club and the A1270 Northern Distributor Road.

The site covers an approximate area of 14.5 hectares (ha) and is located at National Grid reference (NGR) TG 1600 1546.

The site boundary is shown on Figure 1 below:



Figure 1 –The site boundary is outlined in red.

1.2 Aims

This report has been prepared to support a planning application and provides baseline data for an arboricultural assessment of the site and identifies the tree constraints and root protection areas of trees on or near the site which may be affected by future development.

2. TECHNICAL APPROACH

2.1 Arboricultural Survey

The arboricultural survey has been undertaken in general accordance with BS 5837:2012 (ref. **R.1**). The recommendations for tree remediation works are in accordance with current legislation and guidance, including BS 3998: 2010 Tree work – Recommendations (ref. **R.2**).

The data collected during this survey is based entirely upon arboricultural grounds and reflects the condition of the trees on the day the survey was undertaken. The locations of the trees were detailed on a topographical survey provided by the client. All locations of trees are assumed to be correct. Any trees not noted on the topographical plan have been added where appropriate during the tree survey.

Scientific names and common names of plant species identified are as they appear in Stace (ref. **R.3**). For species not listed in Stace, scientific and common names were taken from Johnson and More (ref. **R.4**).

2.2 Soil Assessment

A desk-based assessment of the soil was undertaken to determine potential for volume changing soils on site, using BGS mapping (ref. **R.5**).

2.3 Site Specific Limitations

Trees were surveyed without undertaking vegetation clearance. In cases where the trees were obscured or inaccessible, the parameters which could not be accurately measured were estimated as per BS 5837: 2012 (ref. **R.1**).

3. TREE SURVEY

The survey was undertaken by an experienced surveyor from Geosphere Environmental Ltd on 14 November 2018 to record data relevant to the assessment of the trees on and adjacent to the site.

3.1 Site Description

The site comprises of two large open arable fields bordered by hedgerows and trees of approximately 14.5 hectares (ha). Most of the trees on the site were located adjacent to the boundary of the site with the exception of an old defunct hedgerow comprising of trees and shrubs which separate the northern and southern arable fields.

The site was bordered on the western edge by residential gardens beyond which is a commercial district. To the south is a hedgerow and Taverham Football Club and its associated pitches. The eastern edge of site was bordered by a hedge and a continuation of arable land. The northern edge of site bordered onto the A1270 Northern Distributor Road.

3.2 Tree Survey Results

The results of the tree survey are shown within the Tree Survey Schedule in Appendix 3. A full description of the surveyed parameters is included in the Survey Schedule Description in Appendix 4. A key to the scientific names used is attached within Appendix 5. The results are summarised below:

- A total of thirty-three trees and twelve groups of trees were surveyed;
- Seven trees and two groups of trees were classed as Category A trees. This is the highest classification available under BS 5837:2012. These trees are of high quality and confer particular visual importance on the landscape. These trees are likely to be required to be protected during the development;
- Sixteen trees and six groups of trees were classified as Category B trees. These trees are of moderate quality and confer considerable importance on the landscape. These trees should be retained where possible during development;
- Ten trees and four groups of trees were classified as Category C trees. These trees are of low quality and confer lower levels of benefits to the landscape. The local authority may find it acceptable to remove these trees during development;
- No trees or groups of trees were categorised as Category U trees. These trees are of poor condition and are unlikely to provide significant value to the landscape for more than 10 years. The local authority should find it acceptable to remove these trees during development.

3.3 Tree Constraints Plan

A Tree Constraints Plan Drawing referenced 3551,EC,AR,DS/001/Rev 0 has been prepared for the site and is attached within Appendix 6.

The Tree Constraints Plan describes the constraints that the trees may place on the development. The tree canopy and root protection area have been calculated using the stem diameter as per BS 5837:2012 (ref. R.1).

3.4 Soil Assessment

The BGS digital mapping (ref. **R.5**) indicated that the site comprised of a bedrock layer of Chalk with a recorded superficial layer of Sheringham Cliffs Formation (sand and gravel). A further site investigation should be undertaken to confirm the findings of the BGS digital maps.

In order to minimise the risk, foundations should be designed in accordance to NHBC Standards Chapter 4.2 Building near Trees, (ref. **R.6**).

3.5 Permissions and Council Restrictions

It is not known if there are Tree Preservation Orders present on site. It is advisable to contact the local authority regarding Tree Preservation Orders and Conservation Areas before any tree works are carried out.

4. PRELIMINARY ARBORICULTURAL IMPACT ASSESSMENT

4.1 Proposed Development

A proposed development plan has not been finalised for the scheme at present, however it is understood that the proposed development will comprise of residential housing with associated gardens, with an area set aside for the extension of the sports pitches to the south. An access road is expected to enter the site from the south west and continue through the site to the east. The proposals will incorporate the existing hedgerows and trees into the design where possible. The sections below should be considered when designing the final proposals.

4.2 Potential impacts and avoidance

The residential properties are to be situated within the existing fields, retaining the existing hedgerows and trees. The access roads, houses, driveways, and associated services should all be designed outside of the root protection areas, to avoid impact to the trees.

In order to construct the access road, there will have to be some removals of sections of hedgerow. The location of the road should be designed to avoid as many trees as possible, however, the root protection areas of the category A trees (T1, T3, T7, T8, T12, T19, T33) should be avoided as a priority. The removal of category B or C trees is justified in order to protect the category A trees.

4.3 Tree Management

Standard avoidance measures to reduce the impact of development on trees as required by BS 5837:2012, (ref. **R.1**), is simplified as follows for any development type:

- A Consultant Project Arboriculturalist should be appointed to oversee the arboricultural aspects of the development project;
- The Root Protection Areas, canopies and stems of retained trees must be protected during construction work with barriers as prescribed by BS 5837:2012, (ref. **R.1**). The locations of barriers should be determined once a finalised development plan has been produced;
- Once the protection areas have been finalised and the protective barriers have been erected, then these areas are to be considered construction exclusion zones. Any work within these zones will need prior agreement with the Consultant Project Arboriculturalist;
- Changes to the shape of the canopy of retained trees must be agreed with the Consultant Project Arboriculturalist before any works are undertaken, however, all construction within the canopy extent of a tree is best avoided, to prevent potential damage to future buildings and to avoid recurring pruning regimes;
- Tree planting should form part of the soft landscaping on site to offset any trees which are removed during the development process. An appropriate after care scheme should be implemented to ensure the newly planted trees reach maturity.

4.3.1 Tree Pruning

The site contains a number of trees in various stages of maturity, containing deadwood and fungal infections, usual for trees of their age. Any hazards should be removed prior to the commencement of construction.

The canopies of the trees are likely to require pruning to accommodate new construction. Once the layout of the development area has been finalised, a tree management plan should be completed advising upon remedial action required for health and safety and facilitation pruning for construction needs.

All tree work is to be carried out in general accordance with BS 3998:2010 Tree work – Recommendations (ref. **R.2**) by a professional and specialist arboricultural contractor, who carries the appropriate experience and insurance cover.

Tree planting should form part of the soft landscaping on site to offset any trees which are removed during the development process.

4.3.2 Tree Planting

In order to mitigate the loss of sections of hedgerows and to provide enhancement to the existing trees on site, the hedgerows that are retained within the proposed development, should be repaired and restocked with new trees, to fill in gaps and to create thicker, denser hedgerows. Planting of standard trees should also be included within the hedgerows, with the aim of creating a thick, shrubby hedge, containing mature trees.

Trees should be selected and planted following BS 8545:2014 Trees: From nursery to independence in the landscape – recommendations (ref. **R.7**).

New hedgerow planting should be protected with stock fencing, and appropriate tree guards, to protect the new planting from browsing mammals such as deer and rabbits. It should be expected that some trees will not survive after being planted, so trees should be replaced on a more than 1:1 basis, and an appropriate aftercare programme should be put in place to ensure that any dead trees are replaced. Trees should be selectively thinned and formatively pruned where appropriate after the trees have established. Aftercare should also include mulching and irrigation.

5. RECOMMENDATIONS

The Tree Constraints Plan Drawing ref. 3551,EC,AR,DS/001/Rev 0 in Appendix 6, should be consulted to ensure that the constraints posed by the trees are taken into account when designing the proposed development. For example, retained trees could be incorporated within the proposed residential gardens or within proposed public open space.

Further arboricultural planning is required once the proposed development plans have been finalised. The formal planning process with regards to trees will require the following additional information:

- A Tree Retention Plan should be designed once the layout of the development area has been finalised, and a final proposed development plan is available. This will show the locations of trees which will remain throughout the development works, and the trees which will be removed prior to the commencement of development;
- A Tree Protection Plan should be designed based upon the Tree Retention Plan. This will include finalised locations of protective barriers, construction exclusion zones and any other protection measures that trees will require prior to commencement of construction;
- An Arboricultural Impact Assessment, Arboricultural Method Statement, and Tree Management Plan should be supplied with the Tree Protection Plan. A Consultant Project Arboriculturalist should be appointed by the developer, to ensure all the arboricultural aspects of the redevelopment project are taken into account, from the planning stage onwards.

APPENDICES

APPENDIX 1 – REPORT LIMITATIONS AND CONDITIONS

This report was prepared only for our client and is not intended to be relied on by any other party.

The Executive Summary and Recommendations sections of the report provide an overview and guidance only and should not be specifically relied upon until considered in the context of the whole report.

Interpretations and recommendations contained in the report represent our professional opinions, which were arrived at in accordance with currently accepted industry practices at the time of reporting and based on current legislation in force at that time.

This report is prepared and written in the context stated in the introduction to this report and should not be used in a differing context. Furthermore, new information, improved practices and legislation may necessitate an alteration to the report in whole or in part after its submission. Therefore, with any change in circumstances or after the expiry of one year from the date of the report, the report should be referred to us for re-assessment and, if necessary, re-appraisal.

The trees were not climbed but surveyed from ground level. The survey recorded any defects which were observed, but a full tree health and safety inspection for the site is beyond the scope of this survey.

Any physical changes that happen to the site after the tree survey was undertaken have the potential to invalidate or change the findings of this report. Therefore, the consultant shall not be responsible for any event that may happen after the survey was undertaken due to factors that were not apparent at the time.

Any hazards that were visible on the day of the survey have been noted in the tree management recommendations section of the Tree Survey Schedule (Appendix 3). However, this report should not be considered a substitute for a tree risk assessment or management plan, which would be required to minimize the risk and liability associated with the trees found on site.

APPENDIX 2 – REFERENCES

- R.1.** BSI (2012). BS 5837:2012 Trees in relation to design, demolition and constructions- Recommendations.
- R.2.** BSI (2010). BS 3998:2010 Trees work- Recommendations.
- R.3.** Stace, C. A. (2010). New Flora of the British Isles (third edition), Cambridge University Press.
- R.4.** Johnson and More (2006). Tree Guide, Harper Collins Publishers Ltd.
- R.5.** British Geological Survey (accessed 16 November 2018) Geology of Britain Viewer website: <http://mapapps.bgs.ac.uk/geologyofbritain/home.html>.
- R.6.** National House-Building Council, Standards, Chapter 4.2, 2003 'Building Near Trees'.
- R.7.** BSI (2014). BS 8545:2014 Trees: from nursery to independence in the landscape – Recommendations.

APPENDIX 3 – TREE SURVEY SCHEDULE

TREE SURVEY SCHEDULE

1	2	3	4	5	6				7	8	9	10	11	12	13	14	15	16
Tree No.	Species	Height (m)	Stem diameter (mm)	No. of Stems	Branch Spread (m)				First Branch Height (m)	Canopy Height (m)	Life Stage	Physiological Condition	Structural Condition	Tree Work Recommendations/ comments	Remaining Contribution (Years)	Category Grading	RPA (m ²)	RPA Radius (m)
					N	E	S	W										
# denotes estimated values due to lack of access																		
T1	Turkey Oak	18	570	2	9	9	9	9	2	5	EM	G	G	Minor deadwood in crown	40+	A	147.0	6.8
T2	Pedunculate Oak	12	417	1	4	4	4	4	1	4	SM	F	F	Over-shaded by T1	20+	C	78.7	5.0
T3	Pedunculate Oak #	16	600	1	7	7	7	7	1	5	EM	G	G	Minor deadwood in crown	40+	A	162.9	7.2
T4	Pedunculate Oak #	14	800	1	7	7	7	7	1	4	EM	G	G	0	20+	B	289.5	9.6
T5	Pedunculate Oak #	14	600	2	9	9	9	9	7	4	EM	G	G	Malformation at base	20+	B	162.9	7.2
T6	Pedunculate Oak #	8	250	1	4	4	4	4	2	4	SM	F	F	0	20+	C	28.3	3.0
T7	Pedunculate Oak #	18	600	1	9	9	9	9	3	5	EM	G	G	0	40+	A	162.9	7.2
T8	Pedunculate Oak #	16	705	1	7	7	7	7	3	5	EM	G	G	0	40+	A	224.8	8.5
T9	Scots Pine #	6	100	3	3	3	3	3	1	1	SM	G	F	0	20+	C	4.5	1.2
T10	Scots Pine #	14	300	1	3	3	3	3	2	2	SM	G	G	0	20+	C	40.7	3.6
T11	Scots Pine #	14	300	1	3	3	3	3	2	2	SM	G	G	Considered category B as a group, category C as individuals	20+	B	40.7	3.6
T12	Pedunculate Oak	12	814	1	10	10	10	10	3	3	SM	G	G	0	40+	A	299.8	9.8

TREE SURVEY SCHEDULE

1	2	3	4	5	6				7	8	9	10	11	12	13	14	15	16	
Tree No.	Species	Height (m)	Stem diameter (mm)	No. of Stems	Branch Spread (m)				First Branch Height (m)	Canopy Height (m)	Life Stage	Physiological Condition	Structural Condition	Tree Work Recommendations/ comments	Remaining Contribution (Years)	Category Grading	RPA (m ²)	RPA Radius (m)	
					N	E	S	W											
# denotes estimated values due to lack of access																			
T13	Pedunculate Oak	12	549	1	7	7	7	7	1	4	SM	F	F		0	20+	B	136.4	6.6
T14	Pedunculate Oak	13	575	1	4	4	4	4	5	5	SM	G	G		0	20+	B	149.6	6.9
T15	Pedunculate Oak	13	480	2	4	4	4	4	5	5	SM	G	G		0	20+	B	104.3	5.8
T16	Pedunculate Oak #	13	500	1	5	5	5	5	6	3	SM	G	F		0	20+	B	113.1	6.0
T17	Pedunculate Oak	13	442	1	6	6	6	6	6	3	SM	G	F		0	20+	B	88.4	5.3
T18	Pedunculate Oak	13	360	1	7	7	7	7	6	3	SM	G	F		0	20+	C	58.6	4.3
T19	Pedunculate Oak #	20	1000	1	9	9	9	9	3	3	M	G	G		0	40+	A	452.4	12.0
T20	Scots Pine	20	437	1	4	4	4	4	5	5	SM	F	F		0	20+	C	86.4	5.2
T21	Sycamore	17	763	1	4	4	4	4	5	5	SM	G	G		0	20+	B	263.4	9.2
T22	Scots Pine	18	429	1	4	4	4	4	5	5	SM	F	F		0	20+	C	83.3	5.1
T23	Sycamore	14	473	1	4	4	4	4	5	5	SM	F	F		0	20+	C	101.2	5.7
T24	Scots Pine	10	196	1	3	3	3	3	5	5	SM	P	P	Over-shaded by T23	10+	C	17.4	2.4	
T25	Pedunculate Oak	16	617	1	6	6	6	6	5	5	SM	G	G		0	20+	B	172.2	7.4
T26	Sycamore	14	354	2	4	4	4	4	6	6	SM	F	F	Tree is located off site. There is a large treehouse in tree.	20+	B	56.5	4.2	
T27	Scots Pine #	14	450	1	5	5	5	5	4	3	SM	G	G		0	20+	B	91.6	5.4
T28	Sycamore	16	671	5	6	6	6	6	1	3	SM	G	G	Part of old hedge	20+	B	203.6	8.0	

TREE SURVEY SCHEDULE

1	2	3	4	5	6				7	8	9	10	11	12	13	14	15	16
Tree No.	Species	Height (m)	Stem diameter (mm)	No. of Stems	Branch Spread (m)				First Branch Height (m)	Canopy Height (m)	Life Stage	Physiological Condition	Structural Condition	Tree Work Recommendations/ comments	Remaining Contribution (Years)	Category Grading	RPA (m ²)	RPA Radius (m)
					N	E	S	W										
# denotes estimated values due to lack of access																		
T29	Sycamore	16	671	5	6	6	6	6	1	3	SM	G	G	Part of old hedge	20+	B	203.6	8.0
T30	Sycamore	16	825	5	6	6	6	6	4	5	SM	G	G		20+	B	307.6	9.9
T31	Pedunculate Oak	16	490	1	5	5	5	5	2	5	SM	G	G		20+	B	108.6	5.9
T32	Pedunculate Oak	16	442	1	5	5	5	5	1	5	SM	G	F	Over-shaded by T32	20+	C	88.4	5.3
T33	Pedunculate Oak	18	925	1	12	12	12	12	3	5	EM	G	G		40+	A	387.1	11.1
G2	Hawthorn	0.3	1	1	0.1	0.1	0.1	0.1	0	0	Y	G	G	Newly planted hedge	20+	C	0.0	0.01
G3	Native tree and shrub planting	0.3	1	1	0.1	0.1	0.1	0.1	0	0	Y	G	G	New planting	20+	C	0.0	0.01
G5	Hawthorn, Cherry, Elder hedge	4	100	1	1	1	1	1	0	0	SM	F	P	Gappy hedge. Could be replanted/ repaired	20+	B	4.5	1.2
G6	English Elm, Hawthorn, Elder hedge	8	100	1	1.5	1.5	1.5	1.5	0	0	SM	G	F	Leggy and gappy hedge. Cut, repair and replant	20+	B	4.5	1.2
G7	Scots Pine	18	300	1	4	4	4	4	3	4	SM	G	G		40+	A	40.7	3.6
G8	Scots Pine	18	405	1	4	4	4	4	4	4	SM	G	G		40+	A	74.2	4.9
G9	Scots Pine, Cypress	14	400	1	4	4	4	4	3	1	SM	G	G		40+	B	72.4	4.8
G10	Pedunculate Oak, Hawthorn, Blackthorn	10	150	1	3	3	3	3	1	1	SM	F	F	Scrub and shrubs	20+	C	10.2	1.8

TREE SURVEY SCHEDULE

1	2	3	4	5	6				7	8	9	10	11	12	13	14	15	16
Tree No.	Species	Height (m)	Stem diameter (mm)	No. of Stems	Branch Spread (m)				First Branch Height (m)	Canopy Height (m)	Life Stage	Physiological Condition	Structural Condition	Tree Work Recommendations/ comments	Remaining Contribution (Years)	Category Grading	RPA (m ²)	RPA Radius (m)
					N	E	S	W										
# denotes estimated values due to lack of access																		
G11	Scots Pine	14	300	1	3	3	3	3	2	2	SM	G	G		20+	C	40.7	3.6
G12	Hawthorn, Elder	10	100	1	2	2	2	2	1	2	SM	F	F	Gappy old hedge, now a line of shrubs	20+	B	4.5	1.2
G13	Hawthorn, Apple	6	300	1	3	3	3	3	1	1	SM	G	G	Gappy hedge/ line of shrubs and trees	20+	B	40.7	3.6
G14	Elder, Hawthorn, English Elm, Cypress, Silver Birch, Sycamore, Field Maple	10	300	1	4	4	4	4	3	3	SM	F	F	Trees located off site, adjacent to boundary	20+	B	40.7	3.6

APPENDIX 4 – SURVEY SCHEDULE DESCRIPTIONS

TREE SURVEY SCHEDULE DESCRIPTION

Tree Survey Schedule Description		
Column Number	Heading	Description
1	Tree No.	Sequential reference number (as recorded on the tree constraints plan)
2	Species	Species listed by common name
3	Height (m)	Total height of the tree
4	Stem Diameter (mm)	Stem diameter measured at 1.5 m above ground level in accordance to BS 5837:2012
5	No of stems	Total number of stems of a tree
6	Branch spread (m)	Branch spread, taken at the four cardinal points, to derive an accurate representation of the crown (plotted on the tree constraints plan)
7	First branch hgt (m)	Existing height above ground level of first branch measured at the union with the stem
8	Canopy hgt (m)	Existing height of the average clearance of the canopy above ground level
9	Life stage	The age of the tree determined by life stage category: Y- young, SM- semi-mature, EM- early mature, M- mature, OM- over mature, V- veteran
10	Physiological condition	The physiological condition of a tree based on a tree health assessment: G- good, F- fair, P- poor, D- dead
11	Structural condition	The structural condition of a tree based on structural integrity and signs of structural defects which may cause failure: G- good, F- fair, P- poor, D- dead
12	Tree work recommendations/ comments	Work which is recommended for a tree to improve its longevity and safety in its present context. The recommendations are recorded primarily to assist with the categorisation of the trees. Please see Section 6, Tree Management for further limitations.
13	Remaining contribution (yrs)	Estimated remaining contribution in years that the trees will have on the landscape in their current context. A tree will not necessarily remain safe for the entirety of the remaining years. The remaining contribution has been categorised as follows: <10, 10+, 20+ and 40+
14	Category grading	The trees have been graded as per BS 5837: 2012 recommendations. The grading is formed by a letter and a number. The letter denotes the quality grading of the tree, the number represents one of three sub categories. Sub categories 1, 2 and 3 reflect arboricultural, landscape and cultural qualities respectively. The primary letter grading is as follows: U- Those in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years A- Trees of high quality with an estimated remaining life expectancy of at least 40 years B- Trees of moderate quality with an estimated remaining life expectancy of at least 20 years C- Trees of low quality with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150 mm
15	RPA (m ²)	The root protection area calculated following BS 5837: 2012
16	RPA radius (m)	The root protection area radius calculated following BS 5837: 2012

APPENDIX 5 – KEY TO SCIENTIFIC NAMES

SCIENTIFIC NAMES KEY

Common Name	Scientific Name
Field Maple	<i>Acer campestre</i>
Norway Maple	<i>Acer platanoides</i>
Sycamore	<i>Acer pseudoplatanus</i>
Horse Chestnut	<i>Aesculus hippocastanum</i>
Silver Birch	<i>Betula pendula</i>
Hornbeam	<i>Carpinus betulus</i>
Hawthorn	<i>Crataegus monogyna</i>
Cypress	<i>Cupressus sp.</i>
Beech	<i>Fagus sylvatica</i>
Ash	<i>Fraxinus excelsior</i>
Holly	<i>Ilex aquifolium</i>
Apple	<i>Malus pumila</i>
Scots Pine	<i>Pinus sylvestris</i>
Cherry	<i>Prunus sp.</i>
Blackthorn	<i>Prunus spinosa</i>
Pedunculate Oak	<i>Quercus robur</i>
Goat Willow	<i>Salix caprea</i>
Elder	<i>Sambucus nigra</i>
English Elm	<i>Ulmus procera</i>

Common and scientific names based on Stace (2010) New flora of the British Isles (3rd Edition), Cambridge University Press. For species not present in Stace, scientific and common and names were taken from Johnson and More (2006). Tree Guide, Harper Collins Publishers Ltd.

APPENDIX 6 – DRAWINGS

Tree Constraints Plan – Drawing Ref: 3551,EC,AR,DS/001:1–3/Rev 0



This page is blank

ADDRESS

Brightwell Barns, Ipswich Road, Brightwell, Suffolk, IP10 0BJ

TELEPHONE

01603 298076

FAX

01603 298075

EMAIL

info@geosphere-environmental.co.uk